Northern Bus Garage Reconstruction Project

VIRTUAL COMMUNITY MEETING #3: ENVIRONMENTAL CONVERSATION

11/10/2020

Agenda

- I. Project Team & Schedule
- II. Planning & Design Phase Overview
- **III.** Pollution Minimization
- **IV. Site Remediation**
- V. Environmental Design
- VI. Metrobus Fleet Update
- VII.Next Steps for Project






I. Project Team





Community Meeting Schedule





II. Planning & Design Phase Overview

- The National Environmental Policy Act (NEPA) governs the environmental review process for federally-funded transit projects, including the Northern Bus Garage Reconstruction Project. Three possible classes of action:
 - Categorical Exclusion (undocumented and documented)
 - Environmental Assessment
 - Environmental Impact Statement
- The Federal Transit Administration determined that the project likely would be a Documented Categorical Exclusion.
- Documented Categorical Exclusion document will be released once it is complete and approved by FTA.



NEPA Topics

A Categorical Exclusion considers the following topics:					
Detailed Project Description	Metropolitan Planning and Air Quality Conformity				
CO Hot Spots	Zoning				
Traffic Impacts	Cultural Resources				
Noise and Vibration	Hazardous Materials				
Acquisitions and Relocations	Community Disruption and Environmental Justice				
Public Parkland and Recreation Areas	Ecologically Sensitive Areas/Endangered Species				
Impacts on Wetlands, Floodplain Impacts, Water Quality, Navigable Waterways, and Coastal Zones	Construction Impacts				




Local Historic Preservation Process

- May 2020: Metro presented project design to the Historic Preservation Review Board (HPRB) for conceptual plan review.
- September 2020: HPRB referred the interior demolition permit application for the project to the Mayor's Agent.
- Metro has requested a hearing before the Mayor's Agent hearing officer. (This clearance is necessary to obtain a demolition permit.)
- **December 2020**: Metro will present revised design to HPRB for conceptual plan approval.
- January 2021 (anticipated): Mayor's Agent public hearing. Hearing date has not been set.



Planning Process





Northern Bus Garage Reconstruction: Planning & Design Phase Overview

Question & Answer Period: Planning & Design Phase Overview

- Please submit your questions through the meeting chat
- If the project team is unable to respond to your question during this meeting, you may contact us at <u>MCAP_NBG_Reconstruction_Project@wmata.com</u>
- Summary of the Q&A will be posted to: <u>wmata.com/NorthernBusGarage</u>




III. Pollution Minimization (Air Quality & Noise)

- The air in the bus garage will be "scrubbed" prior to leaving the facility
 - Ventilation system is designed to 'scrub' the exhaust air using specialized exhaust equipment that filters the air.
 - High-speed vehicle entry/exit doors will be used to maintain proper airflow & ensure bus exhaust is treated before exiting into the environment.
- The overhead doors and the building enclosure at the Decatur Street exit will also help to isolate bus operations from adjacent properties and minimize noise levels in the community.
- Metro has eliminated paint booth from project design following community input.



Northern Bus Garage Reconstruction: Pollution Minimization

HVAC & Air Scrubber Locations



PENTHOUSE - INDOOR EXHAUST UNIT W/ DRY SCRUBBER TECHNOLOGY


Stormwater Management

- New 120,000-gallon stormwater detention vault to manage storm flows during heavy rain events.
- New Oil-Water Separator and sand filter to pretreat runoff from buses and cars that is tracked into the building before discharge to sewer system.
- New 60,000-gallon vault system to store captured stormwater for reuse in the bus wash system (significantly reduces potable water use for facility)




Air Quality

Gas-phase Adsorption



The dry scrubber in each exhaust fan system includes a filtration process using disposable high efficiency v bank filters in order to extract contaminants. The v bank filters' chemisorptive process will remove contaminant gases by means of adsorption and chemical reaction.





Fuel Management

- New double lined fuel tanks (2) located underground along Buchanan Street on Metro property
 - Must be located outside the building (NFPA requirement)
 - Each tank will be installed within a concrete vault (rather than in the ground)
 - Multiple leak detection and fuel monitoring systems per tank/vault
 - Tanks will be removed after facility is converted to full Electric Bus Fleet
- Other fluid dispensing systems will have above ground storage tanks with integral leak detection and capture systems.



Northern Bus Garage Reconstruction: Pollution Minimization

Question & Answer Period: Pollution Minimization

- Please submit your questions thorough the meeting chat
- If the project team is unable to respond to your question during this meeting, you may contact us at <u>MCAP_NBG_Reconstruction_Project@wmata.com</u>
- Summary of the Q&A will be posted to: <u>wmata.com/NorthernBusGarage</u>



IV. Site Remediation

The following contaminants have been identified on the project site and will be removed following all requirements/guidelines:

- Soil and Water Contamination
 - Consistent with site history
 - Discussing next steps with DOEE
 - Remediation anticipated
- Lead Paint various surfaces
- Asbestos in floor tiles
- Mercury in thermostats and fluorescent light bulbs
- PCBs in light ballasts
- Underground Tanks (7) Will be removed and 'closed'

<u>See Appendix</u> for more detailed site remediation information.




Northern Bus Garage Reconstruction: Site Remediation

Question & Answer Period: Site Remediation

- Please submit your questions through the meeting chat
- If the project team is unable to respond to your question during this meeting, you may contact us at <u>MCAP_NBG_Reconstruction_Project@wmata.com</u>
- Summary of the Q&A will be posted to: <u>wmata.com/NorthernBusGarage</u>



Rooftop Environmental Features





<u>Key</u>

LEED Accreditation

- Metro is pursuing LEED accreditation for the new Northern Bus Garage
- Recent LEED-certified Metrobus garages projects include:





Northern Bus Garage Reconstruction: Environmental Design

Question & Answer Period: Environmental Design

- Please submit your questions through the meeting chat
- If the project team is unable to respond to your question during this meeting, you may contact us at <u>MCAP_NBG_Reconstruction_Project@wmata.com</u>
- Summary of the Q&A will be posted to: <u>wmata.com/NorthernBusGarage</u>



VI. Metrobus Fleet Update

- Metro operates a fleet of almost 1,600 buses serving neighborhoods and business districts across hundreds of square miles.
- We're committed to incorporating the latest technologies for the safety of our customers and the communities where we operate.
 - All new Metrobuses meet EPA Greenhouse Gas (GHG) emissions requirements: Phase 1 (2012-2016) and Phase 2 (2017-2025)
 - Metro purchases about 100 buses annually
 - More than 800 buses replaced since 2012 (over 50% of current Metrobus fleet)



Zero-Emission Bus Update

Earlier this year, Metro published a <u>Zero-Emission Bus Update</u> that outlines zeroemission fleet planning underway. The transition to zero-emission bus service will require significant regional investment and coordination.

Required actions for the region include:

Energy Infrastructure	Policies & Rate	Funding for Buses &	Washington Metropolitan Area Transit Authority
Investments	Structures	Facility Conversion	
 Identify, fund and build utility infrastructure required to operate service 	 Establish regional policies and energy rate structures 	 Increase funding to replace the existing fleet with cleaner buses 	<text><text><text><text><text><text><text><text><text></text></text></text></text></text></text></text></text></text>



Building for the Future

- Results of the zero-emission bus test and evaluation will allow Metro to identify technologies for adoption pending funding availability.
- The Northern Bus Garage project incorporates design choices that will facilitate electric bus technology conversion, including:
 - Space to accommodate Switch Gear and Transformers
 - Plans for conduit to feed the future chargers
 - Adequate ceiling height to allow overhead electric bus charging



Electric Bus Test and Evaluation Timeline

- Phase 1: Electric Bus Summary Report COMPLETED
 - Research to inform test and evaluation. Covering infrastructure, planning, electric bus fleet and estimated financial costs and requirements.
- Phase 2: Electric Bus Test and Evaluation IN PROGRESS Planned for Shepherd Parkway Bus Garage
 - Vehicle and Infrastructure design:
 - Procurement Process:
 - Bus build and infrastructure upgrades:
 - Performance evaluation:

- Fall 2020 Spring 2021
- Spring 2021 Fall 2021
- Fall 2021 Fall 2022
- Fall 2022 Winter 2023
- <u>Phase 3</u>: Further investment in electric bus technology is highly dependent on test/evaluation results, progress on regional policies, grid infrastructure investments, and funding availability (<u>see Appendix for more details</u>)



Northern Bus Garage Reconstruction: Metrobus Fleet Update

Question & Answer Period: Metrobus Fleet Update

- Please submit your questions through the meeting chat
- If the project team is unable to respond to your question during this meeting, you may contact us at <u>MCAP_NBG_Reconstruction_Project@wmata.com</u>
- Summary of the Q&A will be posted to: <u>wmata.com/NorthernBusGarage</u>



VII. Next Steps for Project

December 2020	January 2021	TBD	TBD
Present final revised design concept to Historic Preservation Review Board	Begin Mayor's Agent process on demolition permit	Execute a Memorandum of Agreement for Section 106 (Historic Preservation)	Submit Documented Categorical Exclusion to FTA for approval

- Updates posted to <u>wmata.com/NorthernBusGarage</u> and shared via email
- Email <u>MCAP_NBG_Reconstruction_Project@wmata.com</u> to join the project's community contact list or request additional information



Northern Bus Garage Reconstruction





Appendix A: Planning & Design Phase Overview



Referenced Reports

Report Description	Released as of 11/9/2020	Report Link	Notes
Documented Categorical Exclusion Report	No	To Be Announced	Not completed; will be completed after HPRB and Mayor's Agent Approvals. Estimated: Late 2021
Zero-Emission Bus Update	Yes	https://www.wmata.com/initiatives/s ustainability/upload/WMATA_Zero_E mission_Bus_Update-02122020- FINAL.pdf	
Site contamination report (bus garage footprint only)	No	To Be Announced	Will be released after DOEE completes its review



Northern Bus Garage Reconstruction

Appendix B: Air Emissions Minimization



Air Quality

Removing Exhaust Fumes Through Chemisorption



Capacity Test Results (typical) @ 99.5% Removal Efficiency						
Contaminant	Media Tested	Capacity, weight %				
Aldehydes	Purafil Select	2.5				
Hydrocarbons	Purakol	21.5				
Nitric Oxide	Purafil Select	5.2				
Nitrogen Dioxide	Purakol	6.6				
Organic Acids	Purakol	22.6				
Sulfur Dioxide	Purafil Select	9.5				










Air Quality

Dual V-Banks in AHUs







Northern Bus Garage Reconstruction

Appendix C: Site Remediation



Site Remediation

- Groundwater and soil environmental investigation:
 - 54 soil borings and 10 temporary monitoring wells
 - water: PCB, BEHP, DRO, and chlorinated solvents and breakdown products
 - soil: PAHs, DRO, lead, arsenic, GRO, ethyl benzene
 - Results forwarded to DOEE; DOEE has asked follow-up questions
 - Project team anticipates remediation
 - During construction: soil removal and water treatment under a DOEE-approved remediation plan
 - After construction: water treatment



Site Remediation (continued)

- Other remediation anticipated:
 - Lead paint: Found on some painted surfaces. All lead paints on retained (historic) surfaces will be removed. Contaminated debris will be separated and disposed.
 - Asbestos: Found in floor tile. Contaminated debris will be separated and disposed.
 - Most other asbestos materials have been abated.



Site Remediation (continued)

- Mercury: Found in fluorescent lights and thermostats. Contaminated material will be removed, separated, and disposed at licensed facilities.
- PCBs: Light ballasts (if identified). Material will be separated and disposed at licensed facilities.
- Existing underground storage tanks (7) will be removed under a DOEEapproved removal and remediation plan.
 - All fluids were removed from all existing underground and above ground storage tanks on the property after the building ceased operations in 2019.




Northern Bus Garage Reconstruction

Appendix D: Environmental Design




Internal Operations – Bus Storage Level



14TH STREET




Internal Operations – Operations Level







Internal Operations – Employee Parking Level





LEED Accreditation

- Metro is pursuing LEED accreditation for the new Northern Bus Garage
- LEED Accreditation status as of November 2020 (pending final design)



Y ? N

LEED v4 for BD+C: New Construction and Major Renovation

Project Checklist Scorecard 40% 201105 Project Name: Northern Bus Maintenance Facility

LEED for Neighborhood Development Location

Surrounding Density and Diverse Uses

Construction Activity Pollution Prevention

Site Development - Protect or Restore Habitat

Fundamental Commissioning and Verification Minimum Energy Performance Building-Level Energy Metering

Fundamental Refrigerant Management Enhanced Commissioning Optimize Energy Performance

Enhanced Refrigerant Management Green Power and Carbon Offsets

Advanced Energy Metering Demand Response Renewable Energy Production

Integrative Process

Sensitive Land Protection High Priority Site

Access to Quality Transit **Bicycle Facilities** Reduced Parking Footprint

Green Vehicles

Site Assessment

Heat Island Reduction Light Pollution Reduction

Outdoor Water Use Reduction

Indoor Water Use Reduction

Building-Level Water Metering Outdoor Water Use Reduction - ACP Indoor Water Use Reduction- ACP Cooling Tower Water Use - ACP

Water Metering

Open Space Rainwater Management

15 1 0 Location and Transportation

redit

hedi

her

Present

11 0 0 Water Efficiency

Prerec

redit

hed

17 4 12 Energy and Atmosphere

1 2 Sustainable Sites

Certified: 40 to 49 points Silver: 50 to 59 points Gold: 60 to 79 points

PI	ať	inu	m	: 8	01	to	11	0

1

16

16

2

5

9	4	0	Materials and Resour	ces	13
Y			Prereq	Storage and Collection of Recyclables	Required
Y			Prereq	Construction and Demolition Waste Management Planning	Required
5			Credit	Building Life-Cycle Impact Reduction	5
1	1		Credit	Building Product Disclosure and Optimization - Environmental Product Declarations	2
1	1		Gredik	Building Product Disclosure and Optimization - Sourcing of Raw Materials	2
1	1		Credit	Building Product Disclosure and Optimization - Material Ingredients	2
1	1		Credit	Construction and Demolition Waste Management	2
10	1	5	Indoor Environmenta	I Quality	16
Y			Prereq	Minimum Indoor Air Quality Performance	Required
Y			Prereq	Environmental Tobacco Smoke Control	Required
2			Credit	Enhanced Indoor Air Quality Strategies	2
3			Gredit	Low-Emitting Materials	3
1			Credit	Construction Indoor Air Quality Management Plan	1
2			Creet®	Indoor Air Quality Assessment	2

	10	1	5	Indoor Environmental	Quality	16
10	Υ			Prereq	Minimum Indoor Air Quality Performance	Required
Required	Y			Prereq	Environmental Tobacco Smoke Control	Required
1	2			Credit	Enhanced Indoor Air Quality Strategies	2
2	3			Credit	Low-Emitting Materials	3
1	1			Credit	Construction Indoor Air Quality Management Plan	1
3	2			Credit	Indoor Air Quality Assessment	2
2	1			Credit	Thermal Comfort	1
1	1		1	Credit	Interior Lighting	2
		1	2	Credit	Daylight	3
11			1	Credit	Quality Views	1
Required			1	Credit	Acoustic Performance	1
Required						
Required	5	1	0	Innovation		6
2	4	1		Credit	Innovation	5
6	1			Credit	LEED Accredited Professional	1
2				-		
1	3	1	0	Regional Priority		4
		1		Credit	Regional Priority: LT- Reduced Parking Footprint	1
33	1			Credit	Regional Priority: § Green vehicles	1
Required	1			Credit	Regional Priority: § Rainwater Management	1
Required	1			Credit	Regional Priority: § Access to Quality Transit	1
Required				-		
Required	78	13	19	TOTALS	Possible Points:	110
6						
18						

WASHING


Northern Bus Garage Reconstruction

Appendix E: Metrobus Fleet Update



Zero-Emission Bus Update

Building upon the efforts of Metro's first-ever Energy Action Plan, released in 2019, and the Washington Area Bus Transformation Project, Metro is engaging in zeroemission fleet planning to enable a clean and sustainable region, control operating costs and improve the customer experience.





Zero-Emission Bus Update

This document lays out the opportunities that zero-emission bus transportation offers the region, reviews actions Metro has already initiated and considers the market, infrastructure and policy prerequisites for success.

The document is available on the Metro website here: <u>https://www.wmata.com/initiatives/sustainability/upload/WMATA_Zero_Emission_Bus</u> <u>Update-02122020-FINAL.pdf</u>



Additional Requirements for Zero-Emission Buses at NBG

- Purchase of electric buses
 - Additional incremental cost per bus (compared with conventional buses)
 - New bus purchases are distributed across the region to balance average fleet age
 - Bus procurement, build and commissioning work
- Additional facility investments
 - New utility connection from grid, switch gear and transformers
 - Bus chargers
 - Fleet charging management system
- Route redesign and investment in on-route charging as required
- Additional external conditions:
 - Electric grid investment to ensure adequate power supply to garage
 - Secure favorable electric vehicle charging rate class from Public Utility Commission

