

WMATA Solicitation FQ16005/WJG
Structural Retrofit of B9 Beam at Farragut North Metrorail Station
Contractor Questions / WMATA Responses

<u>Question No. 1</u>	<u>RFP Section</u>	<u>Question</u>	<u>WMATA Response</u>
1		Is there any specific finish/coat for the cladding?	Refer to Volume 2 – Technical Specifications Section 03495-3 PRECAST GLASS FIBER REINFORCED POLYMER CONCRETE PANELS 2.02 G “Finishes: Exposed panel faces to match existing building concrete column elements or approved samples. Joint marks, grain, or other obvious defects on panel faces are not acceptable.