

WMATA Solicitation FQ16005/WJG
Structural Retrofit of B9 Beam at Farragut North Metrorail Station
Contractor Questions / WMATA Responses

<u>Question No.</u>	<u>RFP Section</u>	<u>Question</u>	<u>WMATA Response</u>
1		Is there any specific finish/coat for the cladding?	Refer to Volume 2 – Technical Specifications Section 03495-3 PRECAST GLASS FIBER REINFORCED POLYMER CONCRETE PANELS 2.02 G “Finishes: Exposed panel faces to match existing building concrete column elements or approved samples. Joint marks, grain, or other obvious defects on panel faces are not acceptable.
2		Can Safety Superintendent and First Aid Attendant be the same full time person?	Yes. Refer to Amendment No. 2.
3		Does the Safety Superintend need to be present at all times if the First Aid Attendant is on site?	Yes. Refer to Amendment No. 2.
4		This is a small project and staffed with two full time Safety professionals, can WMATA re-consider this requirement and eliminate one or the other?	Yes. Refer to Amendment No. 2.
5		Can the Construction General Superintendent act as the Safety Superintendent full-time?	Yes. Refer to Amendment No. 2.
6		Note C11 on A02-5-002 states: “All fabricated structural steel and hardware shall be galvanized.” However Note C12 states: “All fasteners are to be 1” dia. A490 T.C. bolts,” and Per ASTM A490 bolts shall not be coated by hot dip, mechanical deposition, electroplating due to hydrogen embrittlement. Please confirm the finish for all fasteners.	1” diameter A490 TC bolts shall not be galvanized.