Serial Number: RFP-FQ16146/NAC
Date of Issue: May 14, 2018
Original Proposal Due Date: February 3, 2017
Revised Proposal Due Date: May 31, 2018

WASHINGTON METROPOLITAN AREA TRANSIT AUTHORITY
600 FIFTH STREET, N.W.
WASHINGTON, DC 20001

May 14, 2018
AMENDMENT NO. 15
REQUEST FOR PROPOSALS
FOR
POTOMAC YARD METRORAIL STATION
FQ16146/NAC

TO WHOM IT MAY CONCERN:

The Request For Proposals and Proposal Documents accompanying RFP FQ16146/NAC requesting Proposals for the above project are hereby changed in part as listed below.

I. GENERAL INFORMATION

1. This amendment modifies specifications, Standard Drawings and Directive Drawings.
2. This amendment supersedes Amendment 14 (5/3/2018) in its entirety.
3. Proposers may choose (but are not required) to submit revisions to the relevant portions of their technical proposals if warranted by the revised technical requirements provided in this amendment.

II. CHANGES TO DOCUMENTS

The Request For Proposals and Proposal Documents accompanying solicitation RFP/FQ16146/NAC are hereby changed in part as follows:

1. **VOLUME 1 – DIVISIONS 0 AND 1**
Delete the following pages and in lieu thereof add or substitute the accompanying pages:

DELETE	SUBSTITUTE	DESCRIPTION
00 10 00-1 and -4	00 10 00-1 and -4	Revised
00 43 40-1 through -4	00 43 40-1 through -4	Revised
n/a	00 45 10-12	New Page
00 70 00-69	00 70 00-69 through -73	New Pages
01 14 10-2 and -3	01 14 10-2 and -3	Revised

2. **VOLUME 2 – DIVISIONS 2 THROUGH 49**

Delete the following pages and where noted substitute the accompanying pages:

DELETE	SUBSTITUTE	DESCRIPTION
05 12 13	05 12 13	Revised section
07 72 00	07 72 00	Revised section
32 13 00	n/a	Deleted section
32 31 00	n/a	Deleted section

3. **VOLUME 3 – PROJECT DIRECTIVE DRAWINGS:**

Station Platform and Mezzanine floor finish shall be quarry tile. Tile shall be Summitville Tiles, Inc. "10 Summitville Red" 8" hex, 5/8" thickness, flashed, wire cut finish, or approved equal. Grout shall be Summitville #568 "Silhouette" or approved equal.

4. **VOLUME 3 – ST AND DD DRAWINGS:**

1. Delete the precast platform pavers shown on ST-A-STAD-001 and -002. See project directive drawings for platform finish.
2. Delete the illuminated handrails shown on DD-A-VTST-004 and -005. Provide SS handrails without integral illumination in the locations shown.

5. **ACKNOWLEDGEMENT**

Offerors are required to acknowledge receipt of this amendment on the Technical and Price Proposal Forms (Pages 00 41 20-1 and 00 41 30-1) in the space provided. Failure to acknowledge all amendments may cause the bid to be considered not responsive to the invitation, which would require rejection of the Proposal.

for Norie A. Calvert
Contracting Officer

Enclosures

* * * * *